



Please Note: Fabrication will not begin until this drawing is approved, signed and returned to HCI

- ☐ APPROVED  
☐ APPROVED AS NOTED  
☐ REJECTED  
☐ REVISE AND RESUBMIT

By \_\_\_\_\_

Date \_\_\_\_\_

BOTTOM VIEW



(C) 2001 HCI (Heritage Casting & Ironworks). Illustrations are copyrighted. Unauthorized reproduction prohibited. In an ongoing effort to improve quality/design, Heritage reserves the right to modify specifications without notice.

## Approval Drawing

Light Std: F100-L-P407-755-10

**Diffuser Type:** Frosted

**Diffuser Material:** Polycarbonate  
U.V. stabilized.

**Optical System:** Prismatic, heat resistant borosilicate glass refractor, IES Type III.

**Diffuser Holder Material:** Cast Aluminum.  
Diffuser is attached with stainless steel hardware.

**Ballast:** HPS high power factor mounted on removable plate. A quick disconnect wiring system allows for fast easy ballast maintenance.

Wattage - 100W HPS  
Voltage - 120V  
Socket - Medium (4KV).

**Photocontrol:** None.

**Pole:** Astm 513, 11 gauge fluted steel, with 16 flutes. The shaft shall taper from 7" dia at the top of base to 5.5" dia at the top.

**Base Cover:** One-piece ASTM-65-45-0 Ductile Cast Iron attached to pole with four stainless steel bolts.

**Anchor Bolts:** 4 galvanized 3/4" (19mm) x 24" (610mm) long "L" type. Anchor bolts and metal template supplied by HCI.

**Finish:** Electrostatically applied, thermoset polyester powder-coat finish with XL4 four part corrosion inhibiting process.

**Color:** PLEASE SPECIFY

Date: May 03, 2002 Drawing No: 4075  
Model: F100-L-F4-FPC-100HPS-120V-BR-L3-  
-P407-755-10-Color

Project: Urbandale Streetscape

Please Note: Fabrication will not begin until this drawing is approved, signed and returned to HCI



1280 Fewster Drive, Mississauga, Ontario, Canada L4W 1A4  
Tel: (905) 238-2648 Fax: (905) 238-9060  
Toll Free Canada & USA 1-800-267-3175  
E: sales@hclighting.com WEB: www.hclighting.com